



Approvals



INDIAN RAILWAYS
CHITTARANJAN LOCOMOTIVE WORKS
OFFICE OF THE PRINCIPAL CHIEF MATERIAL MANAGER
CHITTARANJAN, WEST BENGAL - 713331

No: 75233865 Dated: - 22/03/2024

Dy.CEE/D-III
CLW/CRJ

SUB: Capacity cum capability assessment of Firm.
REF: LOA NO. STORES / CRJ / 75233865 / 905321
DTD: 16/03/2024

Against Tender Case No. 75233865 opened on 18/12/2023, LOA was issued with capacity cum capability assessment to following firm:-

1.	Tender accepting authority	CMM/M/CLW/CRJ
2.	Item Description & Specification no. and date.	PL NO. 29170096, COPPER TUBE 12.7mm [1/2"] O/D x 1.245 mm WT x 6 METER LONG (Weight/ metre = 0.399 kg). AS PER SPECN.NO. CLW/MS/3/030 Alt.-12. PL NO. 29170114, COPPER TUBE 9.52 mm [3/8"] O/D x 1.245 MM WT x 6 METER LONG. (Weight/ metre = 0.288kg). AS PER SPECN .NO. CLW/MS/3/030 Alt.-12. PL NO. 29170138, COPPER TUBE 6.35 mm [1/4"] O/D x 0.889 mm WT x 6 METER LONG (Weight/ metre = 0.136 kg). AS PER SPECN.NO. CLW/MS/3/030 Alt.-12. PL NO. 29170221, COPPER TUBE 25.4 mm [1"] O/D x 1.651 mm WT x 6 METER LONG (Weight/ metre = 1.096 kg). AS PER SPECN.NO. CLW/MS/3/030 Alt.-12. PL NO. 29170333, COPPER TUBE 38.1 mm [1 1/2"] O/D x 1.651 MM WT x 6 MTR LONG. (Weight/ metre = 1.682 kg). AS PER SPEC.NO.CLW/MS/3/030 ALT.12. PL NO. 29170850, COPPER TUBE 6MM OD X 1mm WT X 6 MTR LONG.(Weight/metre = 0.140 kg). AS PER SPEC.NO.CLW/MS/3/030 ALT.12 AND DRG.NO.1209-08.132-029 REF-2.
3.	Name & Address of the manufacture to whom capacity assessment is to be undertaken.	M/S CALCUTTA GASKETS AND ENGINEERING CONCERN, 56, NETAJI SUBHAS ROAD 4 TH FLOOR ROOM NO. 08, KOLKATA, WEST BENGAL, INDIA, 700001.
4.	Firm's Phone No. / Fax No. & Contact Person	PIYUSH CHANDULAL VOHERA Email: parasmani.savan@gmail.com 919331029312

In view of above CCA may be done when firm apply for the same. After completion of CCA a copy of Registration Certificate, may be sent to this office for further action.

SMM/M/CLW/CRJ

COPY TO:-

- 1) CEE/D&D/CLW/CRJ for kind information please.
- 2) M/S PARASMANI TUBES PVT. LTD. / VELSAD, 5/2 GIDC, PHASE -I, UMBERGAON, VELSAD GUJRAT - 396171, VELSAD - 396171, Ph No - 9331029312
- 3) M/S CALCUTTA GASKETS AND ENGINEERING CONCERN, 56, NETAJI SUBHAS ROAD 4TH FLOOR ROOM NO. 08, KOLKATA, WEST BENGAL, INDIA, 700001, Ph No - 9331029312

Your offer is under active consideration for developmental order subject to successful capacity cum capability assessment, acceptance and approval by the competent Authority. You are advised to approach Dy.CEE/D-III/CLW/CRJ for capacity and capability assessment.


SMM/M/CLW/CRJ



Approvals

CIN No. U74899DL 1995GOI068150



दिल्ली मेट्रो रेल कॉर्पोरेशन लि०
DELHI METRO RAIL CORPORATION LTD.

(भारत सरकार एवं दिल्ली सरकार का संयुक्त उपक्रम)
(A JOINT VENTURE OF GOVERNMENT OF INDIA AND GOVT. OF DELHI)

No: DMRC/Elect/Patna Metro/GM/PE-02/VT(A)(VAC)/544/2115

Date: 09.12.2024

To,

M/s Tuaman Engineering Limited,
23-A, Netaji Subhas Road, Fortuna Tower,
8th floor, Kolkata-700001, India
Tel No.: +91-8794237470
Email ID: kamal.kant@tuaman.co.in

(Kind Attention: Mr. Kamal Kant, CPM)

Sub.: PE-02: Design verification, detail engineering, supply, Installation, testing and commissioning of Electrical & Mechanical systems, fire detection, fire suppression system & DG sets of Corridor-01 & Corridor-02 of elevated station and depot of Patna Metro Rail Project. – Manufacturing clearance for VAC copper pipe & Insulations- reg.

Ref:

- LOA No. DMRC/20/III-748/2020, Dated: 12.10.2021
- M/s TEL letter no. TEL/SITE/PE-02/DMRC/24-25/735 dated 26.11.2024.

Dear Sir,

Vide above reference (ii), M/s TEL has submitted the sample for VAC Copper pipes with insulation for approval of DMRC which was inspected by DMRC and observed the sample is in line with the contractual requirements.

Therefore, samples are being 'Approved', to be used for E&M work of Depot and Elevated station and of DMRC Patna Metro Rail Project under contract PE-02 only. The details & make of sample is as under: -

Sl. No.	BOQ No	Items	Make/Model	Remarks
1.	E.11.11.7	Refrigerant Piping with fire rated Class 'O' Closed cell elastomeric nitrile rubber type tubular insulation with 0.63mm aluminium sheet cladding for following sizes: 1. 41.3mm OD (insulation-19mm) 2. 34.9mm OD (insulation-19mm) 3. 28.6mm OD (insulation-19mm) 4. 25.4mm OD (insulation-19mm) 5. 22.2mm OD (insulation-13mm) 6. 19.1mm OD (insulation-13mm) 7. 15.9mm OD (insulation-13mm) 8. 12.7mm OD (insulation-13mm) 9. 9.5mm OD (insulation-13mm) 10. 6.4mm OD (insulation-13mm)	Parasmani Tubes Pvt. Ltd. (PTP-K-Series)	Test certificates shall be submitted before/during FAT
2.		Fire Rated Class 'O' Closed cell elastomeric nitrile rubber type Tubular insulation – (UL/FM Approved)	K-Flex (ST Tubes)	

Page 1 of 3

कार्यालय : गाँधी मूर्ति कम्पाउण्ड, एनर्जी पार्क के नजदीक, पटेल नगर, पटना-800023 (बिहार)
Office : Gandhi Murti Compound, Near Energy Park, Patel Nagar, Patna - 800023 (Bihar)

KERALA PUBLIC WORKS DEPARTMENT (ELECTRICAL)		
	Electrical AC Work	
	Acceptable list of Materials	
	Name of work	GENERAL-Health Department - Annual Plan 2023-24 - Implementation of Plan scheme 'Developing Super Speciality Facilities - Various electrical works in Super Speciality Block (4th floor) - A A Rahim Memorial District Hospital, Kollam-Electrical AC Work
Sl.N	Material Description	Make
	AIR CONDITIONING SYSTEM	
1	AC Indoor unit (split / High wall/Cassette/High Static Ductable unit)	Mitsubishi /Daikin/Carrier/LG
2	AC Out door unit (DX/VRF/VRV/Chiller unit	Mitsubishi/ Daikin/Carrier/LG
3	AHU	Systemair/VTs/ Edge-Tech/Zeco//LUFTECH
4	Refrigerant Gas	Dupont/Value
5	CONTROL CABLE /POWER CABLE	Finolex/ Havells/KEI/RR cable/Traco
6	ALUMINIUM DUCTS /GSS sheet	Jindal/Sail/ Tata/ Hindalco
7	COPPER PIPE	Parasmani/mamdav/Totaline/Mexflow
8	DUCT THERMAL INSULATION	Armacell/ K-Flex/ Superlon/Phenolux/Supreme
9	DUCT ACOUSTIC INSULATION	Armacell/ K-Flex/ Superlon
10	GRILLES, DIFFUSERS, LOUVERS,	Systemair/ Caryaire/ Cosmic/ Airmaster/Excel
11	AIR FILTERS / HEPA FILTERS	Aerofoil/ Dyna/ Thermodyne/ AAF,/Pyramid
12	EXHAUST / DUCT FANS	Kruger/Nicotra/ Systemair/ Caryair/ Greenheck/Ostberg
13	PVC Conduit(ISI Marked) Ivory colour	Konseal/ESPEE/Balco/Toms
14	PVC accessories(ISI Marked) Ivory colour	Toms/Presfit/Spin-tech/Balco
15	FRLS PVC insulated Copper Wire/Flex Wire(ISI marked)	Traco/KEI/Lapp //RR/ /Bonton/Gloster
16	U.G. cables (ISI marked)	RR / Gloster/Havells/KEI/Traco
17	Cable Gland/Socket	Siemens/Dowells
18	Boxes for Modular Accessories /Front Plates/Modular type switches, Plug/sockets, Plug Top	MK-Blenze/ Legrand-Lyncus/ LK- entice
19	CMS	OBO/ MK/ Legrand

Contractor

Chief Electrical Engineer